SYNTHETIC: site scenario for method statement and risk assessment

Invented for training. Not for use on any site.

Activity: excavate a trench and lay 450 mm concrete surface water pipe beside a public road.

- Trench about 1.8 m deep and 1.2 m wide, 60 m long, excavated in 20 m sections
- Ground: soft clay, water table near the base, rain forecast for two of the five days
- One 20-tonne excavator, one dumper, a plate compactor, a pipe-laying crew of three, a banksman
- A live water main crosses the line of the trench near the third section. Its exact position has not been confirmed. An electricity cable runs along the opposite verge
- A footpath runs beside the works and a primary school entrance is 80 metres away. School starts at 9.00 and finishes at 14.30
- One lane must stay open with temporary traffic lights
- A stream runs about 15 metres from the trench at its closest point
- Spoil is stored on site and the surplus taken to a licensed tip